

SR 581 Intersection Improvement at SR 54 441099-1-52-01

Project Details	
Work Type	Intersection Improvement
Phase	Completed
Limits	from south of Eagleston Blvd to SR 54
Project Start	September 22, 2022
Length	.2 miles
City	Wesley Chapel
County	Pasco
Road	Bruce B Downs SR 54 SR 581
Construction Cost	\$2.1 million
Estimated Completion	May 30, 2023
Contractor	Cone and Graham, Inc.

Contact Information	
Project Information	John McShaffrey 813-975-6930 roadwork@dot.state.fl.us
Media Contact	Kris Carson 813-975-6060 Kristen.carson@dot.state.fl.us



About

As of May 30, 2023, all work was completed and this project was final-accepted from the contractor.

This project made improvements to SR 581 (Bruce B. Downs Blvd.) from south of Eagleston Blvd. to SR 54. The improvements included closing the existing median at the shopping plaza entrance, extending the northbound left turn lane to SR 54, adding a traffic signal at Eagleston Blvd., adding a southbound U-turn lane, and adding pedestrian upgrades at the Eagleston Blvd. intersection with SR 581.

New Traffic Signals are Operational!

The traffic signals at the intersection of SR 581 (Bruce B. Downs Boulevard) and Eagleston Boulevard (first intersection south of SR 54) were put into full operation Monday morning, May 22, 2023.