

I-75 Ramp Reconfiguration and Interchange Modification from SR 574 (MLK) to I-4

429251-1-52-01

| Project Details | |
|-----------------------------|-------------------------------|
| Work Type | Interchange modification |
| Phase | Construction |
| Limits | From SR 574 (Exit 260) to I-4 |
| Project Start | August 19, 2021 |
| City | Tampa |
| County | Hillsborough |
| Road | I-4 I-75 |
| Construction Cost | \$89.7 million |
| Estimated Completion | Summer 2025 |
| Contractor | Prince-Ajax DDI JV |



About

This design-build project is building a barrier separating northbound I-75 travel lanes from traffic entering and exiting the interstate between the SR 574 (Dr. Martin Luther King Jr. Boulevard) and I-4 exits ramps in Hillsborough County.

A two-lane northbound collector-distributor (CD) roadway is being built east of the current northbound travel lanes within the existing right of way. Traffic entering and exiting northbound I-75 at SR 574 (Dr. Martin Luther King Jr. Boulevard) and I-4 will use the new CD roadway.

In addition, the SR 574 (Dr. Martin Luther King Blvd) interchange will be converted to a diverging diamond interchange.

These changes will improve the efficiency and safety of the interstate in this area.

Construction activities are expected to finish during summer of 2025.

| Contact Information | |
|----------------------------|---|
| Project Information | Maricelle Venegas 813-975-6204 RoadWork@dot.state.fl.us |
| Media Contact | Kris Carson 813-975-6060 Kristen.Carson@dot.state.fl.us |