

I-75 Ramp Reconfiguration and Interchange Modification from SR 574 (MLK) to I-4

429251-1-52-01

Project Details	
Work Type	Interchange modification
Phase	Construction
Limits	From SR 574 (Exit 260) to I-4
Project Start	August 19, 2021
City	Tampa
County	Hillsborough
Road	I-4 I-75
Construction Cost	\$89.7 million
Estimated Completion	Summer 2025
Contractor	Prince-Ajax DDI JV

Contact Information	
Project Information	
Maricelle Venegas 813-975-6204 RoadWork@dot.state.fl.us	
Media Contact	
Kris Carson 813-975-6060 Kristen.Carson@dot.state.fl.us	



About

This design-build project is building a barrier separating northbound I-75 travel lanes from traffic entering and exiting the interstate between the SR 574 (Dr. Martin Luther King Jr. Boulevard) and I-4 exits ramps in Hillsborough County.

A two-lane northbound collector-distributor (CD) roadway is being built east of the current northbound travel lanes within the existing right of way. Traffic entering and exiting northbound I-75 at SR 574 (Dr. Martin Luther King Jr. Boulevard) and I-4 will use the new CD roadway.

In addition, the SR 574 (Dr. Martin Luther King Blvd) interchange will be converted to a diverging diamond interchange.

These changes will improve the efficiency and safety of the interstate in this area.

Construction activities are expected to finish during summer of 2025.